



LOFAR System Overview

Michiel van Haarlem
Technical Project Scientist
(ASTRON)

LOFAR Technical Concept




- LOFAR is a very large distributed radiotelescope:
 - 13,000 small antennas
 - in 77 stations
 - >20 Tbit/sec raw data
 - >40 Tflop supercomputer
 - innovative software systems
 - datamining and visualisation
- Full and exclusive control via the Internet
- Instantaneous view of the full sky, several simultaneous users.
- Pathfinder for the SKA in many respects




Configuration





32 Core Stations
3x2 km



Dataflow View







Stations



Remote Station Architecture




Optional
10- 30 MHz




30-80 MHz




120-240 MHz







Low Band Antenna (30-80 MHz)





High Band Antenna (120-240 MHz)







Remote Station Processing Board



- 90 nm technology
- 192, 18x18 multipliers
- 2.6 Mbit RAM
- 1020 "balls" on chip



Remote Station Hardware Numbers




- 96 dual polarization low band antennas
- 96 dual polarization high band tiles
- 192 receiver boards
- 24 digital signal processing boards
- 12 transient buffer boards
- 6 backplanes
- 6 clock boards

Key Numbers



Description	Value	Unity
# subbands	512	
Max. number of beams (B = 4 MHz)	8	
Min. number of beams (B = 32 MHz)	1	
A/D converter resolution	12	bit
Sample frequency	200 / 160	MHz
Number of polarizations	2	
Output word width (complex)	16+16	bit
Aggregate output bandwidth	32	MHz
Output data rate	2048	Mbit/s
Transient buffer storage period	1	s

Description	Value for fs of		Unity
	160 MHz	200 MHz	
Subband width	156	195	kHz
Number of beamlets	206	165	







Network & Central Processor



Wide Area Network




- Data transport from stations and central core to central processor facility
- Dedicated fiber connection between core and central processor
 - ☞ up to 800 Gbps bandwidth
 - ☞ 10 GbE CWDM
 - ☞ 8 channels
 - ☞ length ~70 km
- Remote station connections:
 - ☞ 10 GbE technology
 - ☞ data rate 2 Gbps from antennas + monitoring + other sensors



CEP Implementation Model




- Multiple sub-clusters with task-optimised hardware
- BlueGene inside



Input Section




- Receive data streams from remote stations
- Connections to WAN: raw 1 GbEthernet
- Input buffering and Synchronisation
- Embedded frequency separation filter
- Routing / Transpose
 - 320 Gbps All-to-All connection scheme
 - e.g. on Infiniband



Auxiliary processing




- Control / tune processing pipelines
 - Fringe stopping
- Typical analysis applications
 - RFI detection & mitigation
 - Ionosphere calibration
- On-line modeling & analysis
 - e.g. Transient detection
- Resource pool, is scalable



Storage system




- Collect data streams into data sets
- Temporary storage of datasets (typically 2 days)
- Data input from
 - processing lines
 - off-line processing applications
- Data output to
 - off-line processing tasks
 - Data export & archiving



Off-line processing




- General purpose resources
- Typical tasks:
 - calibration
 - Imaging
 - interpretation
 - product generation
- Optimised resources for Selfcal and Imaging possible



On-line pipeline processing




- Issues:
 - power/heat, volume, memory etc.
 - limited programming environment
- Massive processing power for
 - 8 bits complex multiplication and addition
- Simple applications scheme
 - pipes-and-filters style
 - operate in slave mode
- Simple data transformations
 - correlator
 - beamformer



Subsystems: Blue Gene/L



- 6 racks
 - 128 IO nodes and 1024 compute nodes per rack
 - Internal Tree and Torus (175 MB/s * 6 directions)
 - Compute node
 - Dual core
 - 512 MB RAM
 - IO node
 - 1 GbE connection
 - Connected to 8 compute nodes
 - Diskless
- 1 Service Node (p650 + DB2)
- 8 Front-End nodes for development




Blue Gene/L installation April 2005




Compute Card



Dual Node Compute Card



Node Board



BlueGene (half) Rack

512 Way BG/L Prototype





midplane = half rack




Software & Operations





Model calculations on the other 2 BG racks




- Multiple observations run concurrently
- Applications have different lifetimes
 - service providers (green)
 - observation specific (yellow)
- On-line and Off-line applications scheduled independently

The Calibration Challenge



- 25 TByte of data
 - 10^{13} samples
- Models of
 - Instrument
 - Ionosphere
 - Sky sources
- Vary in time, freq., ...
- ~100 000 parameters
- Correctly model physics
 - Image plane effects
 - Instrument behaviour etc.
- Complex minimalisation problem!




Major Observing Modes





- Synthesis Mode - imaging - data cubes
 - like Westerbork, VLA, GMRT
 - long baseline mode
 - core-only mode (EOR, All-sky monitor)
- Tied Array Mode - pulsars - time series
- Transient Modes
 - Raw time series - antenna data stream
 - Beamformed data - selected sub-bands

The next deliverable: CS1



- Hardware of 1 station
- Distributed over 4 station locations
- 12 Gbps connection to Groningen
- Downscaled CEP installation



Initial CS-1 Experiments



1. Correlate and integrate data with 1kHz, 10 sec resolution of all microstations (LBA) and store UV data
2. Create non-calibrated images on 10 sec time scales and copy them to an archive
3. Switch on On-line calibration pipeline on CEP
4. Copy UV data to a GRID

Timeline



- CS1 hardware: June 2006
- CS1 commissioning June-July 2006
- CS1 operation from June onwards

- CS1 software second release September
 - Increased usage of Stella system (up to 4 racks)

- Rollout of Core stations from end 2006 onwards
 - Stella usage grows to 4 rack steady; 6 racks

Project Schedule



- April 2006: CS-1 Roll-Out Review
 - Station infrastructure, EMC, Power, Cooling
- October 2006: System Critical Design Review
- Q1 2007: Completion of First Core Stations
- Mid 2008: Core Beamformer Upgrade
- Q1 2008: Completion of First Remote Stations
- Q4 2008: Roll-Out Completed

